

**FEATURES** 

- Link turn-up with the far end DSLAM
- Detailed Modem Status
- Link Measurements
- Ping & Echo Ping Features

### **BENEFITS**

- Lightweight
- Flexible modular design
- Leverages existing MTT platform
- Cost-effective and future-proof

### PRODUCT DESCRIPTION

Module Size (WxLxH): 5.0 x 3.5 x 0.9 in (12.6 x 9 x 2.2 cm) Operating Temperature: 32° to 122°F (0° to 50°C) Storage Temperature: -4° to 158°F (-20° to 70°C)

Humidity: 5% to 85% noncondensing

## **SPECIFICATIONS**

### Chipset

Conexant Accelity Packet EoVDSL CPE

### **Supported Technologies**

VDSL (ITU-T G.993.1, ANSI T1.424)

### **Connectors**

VDSL Line Interface: RJ-11 @ 100Ω



# SUNRISE TELECOM

# VDSL2 VTU-R Module

SSMTT-41\

**Data Sheet** 

VTU-R

Customer Premises

VTU-O

VTU-O

Central Office

The SSMTT-41V VDSL VTU-R Module, part of the SunSet® Modular Test Toolkit (MTT) family of products, is a rugged, battery-operated handheld test solution for the installation and verification of VDSL networks. A complete set of testing capabilities makes the SSMTT-41V ideal for the field technician who needs VDSL installation and service verification, and connectivity verification in a single, lightweight handheld unit. The wide range of test functionalities of the SSMTT-41V Module provide all of the tools needed for bringing up and servicing VDSL lines.

### **VTU-R Features**

**Modem Status Measurements** 

Fast Path Rate

Interleaved Path Rate

Maximum Attainable Rate

SNR Noise Margin

Capacity

Attenuation

**Output Power** 

Delay

Link Measurements

Counters for CRC, FEC, and HEC events

Counters for LOS, SEF, NCD, OCD, BER

Errored Seconds, Severely Errored Seconds, Unavailable Seconds

Number of Link Drops

Bits/SNR per Tone: Full graphical and tabular display

Band Plan Selection: Plan 998, Plan 997

Programmable via downloaded files for Pass/Fail parameters

Pass/Fail assessment/indication

Safe Mode: Compatible with Alcatel LightSpeed DSLAM

### **IP** Features

### Ping Test

Statistics on PING messages

Number of sent/received/missing/unreached messages

Current/average/max/min round trip delay

Test Result: Pass/Fail assessment

### Echo Response

Automatic PING Echo response and record

### ORDERING INFORMATION

SSMTT-41V VDSL2 VTU-R Module. Includes PING Testing.

### Recommended Cable

SA297 Cable, RJ-11 6-pin to Blk/Red Bed-of-Nails Clip, 6'