_____CF-30AC

FAST · SAFE · RELIABLE



25 AMP AC GROUND CONTINUITY AUTOMATIC PRODUCTION LINE TESTER

Features

- AC Output. Constant current delivers 25 amps to any ground circuit with resistance of 0 to 0.1 ohms.
- Logic controlled, one button test. Lights indicate test results. Upon failure , buzzer sounds and testing is terminated.
- V=irtual voltage sense circuit compensates for lead resistance.
- High efficiency design results in low power consumption.
- Calibration resistor mounted on rear panel.
- Performs to CE, IEC, TUV safety agency requirements for production line testing.

- Factory adjustable for current levels of 10 30 amps.
- Ergonomically designed for safety, speed and efficiency.
- Compact and durable.
- Test leads included.
- One year calibration cycle.
- 30 day trial 1 year warranty.
- TEST-LINK Compatible.





www.compwest.com

- GF-30AC



ELECTRICAL

Output:

Pass/Fail Criteria:

Pass/Fail Repeatability: Ramp Time: Overshoot: Test Duration Timer; Duty Cycle: 25 Amps ac \pm 3% into any load - short circuit to 100 milliohm

100 - 150 milliohms user adjustable. 100 milliohm calibration resistor supplied.

± 3% 10 msec None 0 - 10 sec. approx. 100%

ENVIRONMEN TAL

Operating Temperature:

Relative Humidity Range:

15-40°C

GENERAL

Input Power Requirements: Dimensions: Weight: 0-90% non-condensing

108 - 127 or 216 - 254 volts, 50/60 Hz 9.250 (W) x 4.250 (H) x 10.000 (L) in. 12 lbs.

7915 Silverton Avenue, Suite 315, San Diego, CA 92126 Phone: (858) 860-0277 Fax: (858) 860-0279 E-mail: sales@compwest.com Visit Us At: www.compwest.com

